CHITALDROOG DIVISION.

ADVERTISEMENT.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldroog Division, up to 10th November 1891, for the construction of a new tank across Madirhalla near Vuduvalli, Hiriyur Taluk, the estimate for which has been sanctioned. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1894.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldroog between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

Items of Work.	Per.	Quantity.	Rate.	Cost.	Total of each.	Grand Total.
Bund—						
Earthwork	C. Yd.	92,102				
Do filling halla	Do	23,478				
New stone work for revetment ..	Do	5,002				
Removing silt and baling water and cutting grips in rock	Lump	Sum.				
Grade stones	Each.	22				
B. M. stones	Do	2				
Tank No. stone	Do	1				
Gauge stone	Do	1				
Sluice—						
Brick in surki mortar	C. Ft.	4,762				
Stone in chunam	Do	592				
Slab stones	S. Ft	1,093				
Archwork in brick	C. Ft.	236				
Plastering with surki mortar	Sqr.	14·30				
Plug with chain	Each.	4				
Lifting gear with wooden shutter, complete..	Do	2				
Cutting orifices and holes in cross stones ..	Do	8				
Iron plate steps fixed in the abutment ..	L. S.	..				
Centring arch	Do	..				
Waste Weir—						
Kodi	Do	..				
Distribution—						
Opening out Irrigation channel ..	Do	..				
Miscellaneous—						
Cost of deviation of road	Do	..				

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for construction of a new tank near Vuduvalli," in default of which, tenders will be rejected.

5 The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

D. RANGA RAO,
Offg. Executive Engineer.